

No. EEC/BSNL/JPR/ 2024-25/264

Dated: 08.07.2024

NOTICE INVITING QUOTATION

EEC/BSNL/JP/NIQ-01/2024-25


Sealed item rate quotations are invited by the Executive Engineer(C) BSNL Civil Division **QUARTER no R1/R3 P & T Colony C- scheme JAIPUR** on behalf of BHARAT SANCHAR NIGAM Limited (A Government of India Enterprises) from registered firms for the work "Dismantling and carriage of 27 M roof top tower from plot no. 698, Main Jagat Siromani Road, Amer (JAI015) GSM site to Pratap Nagar Store at Jaipur".

The quotation papers can be obtained from the office of the Executive Engineer (C), BSNL Civil Division **QUARTER no R1/R3 P & T Colony C- scheme JAIPUR** up to **1.00 PM** on **12.07.2024** and duly filled quotations along with requisite papers will be received up to **3:00 Pm** on **12.07.2024** and will be opened on the same day at **3:30PM**.

Time Schedule- The time schedule for the work is fixed as 7(Seven) days from the date of award. The Firms shall strictly adhere to the time frame.

Conditions:-

- 1) The rates are net and inclusive of all taxes.
- 2) a) Income tax, Professional tax, any other tax as per Statutory Provisions of Govt. of India and Rajasthan State Govt. shall be deducted by the BSNL from the bill. A certificate in this regard shall be furnished by the BSNL.
b) Service Tax if applicable has to be indicated in the bill separately with Total amount giving the Service Tax registration No. and other particulars.
- 3) No counter conditions should be included in bid. Conditional bid will be summarily rejected.


Executive Engineer(C)
BSNL Civil Division-Jaipur

Copy to:

1. The Addl. C. E. (C), BSNL Civil Circle, Jaipur and Superintending Engineer (C), BSNL Civil Circle, Jodhpur.
2. The Executive Engineer BSNL, Civil Division, Udaipur./Jodhpur/Bikaner.
3. The E.E. Postal Civil Division. 1st floor C.P.M.G building, Sardar Patel Marg, Jaipur.
4. The E.E. CPWD, Jaipur.
5. The SDE BSNL, Civil Sub Division-I/II, Jaipur /ALW/JJN.
6. The AGM (MM), O/o CGMT, BSNL, Jaipur
7. The AGM (Plg) O/o PGMTD, BSNL, Jaipur
8. The A.O. (cash) O/o PGMTD, BSNL, Jaipur
9. Notice Board.


EXECUTIVE ENGINEER(C)

SCHEDULE OF QUANTITY

Name of the work : Dismantling and carriage of 27 M Roof top tower from plot no 698, Main Jagat Shiromani Road, Amer (JAI015) GSM site to Pratapnagar store at Jaipur.

NIQ No. :-EEC/BSNL/JP/NIQ-01/2024-25

S.No.	Description of Item	Quantity	Unit	Quoted Rate in Figure (Rs)	Quoted Amount (Rs)
1	Dismantling & dismembering of Roof Top Tower consisting of structural steel work bolted in built up section (upto 27 m height of tower) including cutting of nuts/bolts if required, dismembering of wave guide, ladder etc complete.				
1.01	27 M RTT (JAI015). (Site add: Plot no 698, Main jagat Shiromani Road, Amer, Jaipur)	1.00	Job		
	Notes :The items includes for the following and nothing extra shall be paid on this accounts.				
	(a) The agency shall take every precautions against the damages to the structure or near by structures while dismantling / dehoisting the tower.				
	(b) Necessary safety precautions to protect the human-lives, insurance coverage to the labours etc. shall be the sole responsibility of the agency.				
	(c) Nuts / bolts and washers dismantled shall be collected size-wise and kept in separate gunny bags				
	(d) Item includes all operations, tools & plants, equipments, machinery etc. required for the work as well as safety measures as per the relevent IS codes.				
2	Extra for number painting on each member of dismantled above item no. 1 tower material etc as per direction of Enginner-in-Charge. (For 15m RTT & 18m RTT).	1.00	One Job		
3	Carriage of RTT (27m) material and antenna, ladder etc. including loading, unloading from Main jagat Shiromani Road, Amer Jaipur to Telecom Store at Pratapnagar, jaipur upto 30 Km lead approx weight 7.50 Metric tonne i/c handing over all material as directed.	1.00	One Job		

S.No.	Description of Item	Quantity	Unit	Quoted Rate in Figure (Rs)	Quoted Amount (Rs)
4	Disposal of building rubbish/malba/similar unserviceable dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial head, for all leads including all lifts involved.	2.00	One Cubic Metre		
5	Credit to the department for unserviceable reinforcement received from dismantling and other iron scrap etc.	100.00	Per Kg.		
6	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge.	3.00	One Cubic Metre		
7	Extra for cutting reinforcement bars manually/ by mechanical means in R.C.C. or R.B. work (Payment shall be made on the cross sectional area of R.C.C. or R.B. work) as per direction of Engineer in-charge.	5.00	One Square Metre		
8	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead :				
8.01	With cement mortar 1:4 (1cement: 4 coarse sand).	15.00	One Square Metre		
		Total Rs.			

Executive Engineer (C)
BSNL Civil Division,
Jaipur