

**BHARAT SANCHAR NIGAM LIMITED**  
(A Govt. of India Enterprises)  
O/o The Executive Engineer (Civil),  
BSNL Civil Division, ,  
Admin bldg .Subhash Nagar, Jodhpur – 342008.

**NOTICE INVITING QUOTATIONS**

The Executive Engineer (Civil), BSNL Civil Division- , Room No109 ,Admin bldg Ground floor .Subhash Nagar, Jodhpur, invites, on behalf of the Bharat Sanchar Nigam Limited, sealed/taped item rate quotations for the work of “Providing and laying RCC roof slab over pump room in M/W bldg camus shastrinagar, Chittorgarh..” from the approved and Enlisted eligible Contractors in the appropriate class in BSNL (Civil Wing), DOT (Civil Wing), DOP (Civil Wing), CPWD, MES, Rajasthan state PWD (B&R) all having experience of similar type works.

The quotations / schedule of quantities may be had from this office during 11.00 hrs to 14 hrs upto dated 15.07.2024. The duly filled quotations should be reached to this office on dated 15.07.2024 at 15.00hrs, which will be opened on same day at 15:30hrs.

Estimated cost :- Rs. 55912/-

**Conditions:**

1. The work has to be finished within 15 days after issue of work order.
2. The rates quoted by the agency shall be inclusive of all types of taxes / levies / duty and GST as applicable by the Govt. including labour Cess and nothing extra shall be payable on such account. The Contractor, as service provider, shall be fully responsible for any default in payment of this tax.
3. The rates quoted by the agency shall be inclusive of 1 % (one percent) BOCW cess on the work done and shall be recovered from running / final bill as applicable on the building and other Construction workers welfare Cess Act, 1996 due to introduction of “The Building and other Construction Works Regulation of Employment and Conditions of Service Act 1996”.
4. Agency will comply the provisions of EPF & Misc. Provisions Act 1952, Employees Provident Fund Schemes 1952 and the ESI Act, 1948 in respect of labourers/employees engaged by them for performing the work.

NIQ NO. 07/EE/BSNL-CIVIL/JDR/ 24-25/

Dated 12.07.2024

-SD-  
Executive Engineer (C)  
BSNL Civil Sub Division,  
Jodhpur

File No 9(07)/EE/BSNL-CIVIL/JDR/ 24-25 / 80

Dated 12 .07.2024

Copy forwarded for information:-:

1. The Chief Engineer (C), BSNL Civil Rajasthan zone, Jaipur.
2. The Additional Chief Engineer (C), BSNL Civil Circle, Jodhpur/Jaipur,
3. The EE (C), BSNL Civil Division, Bikaner/Jaipur/Udaipur.
3. The IFA to Civil Division, O/o The GMTD, BSNL, Jodhpur
4. The SDE (C), BSNL Civil Sub Division –Jodhpur/ Barmer/Ajmer.
5. The Accounts Branch-I,II , O/o EE (C), BSNL Civil Division, Jodhpur.
6. Notice Board, O/o EE (C), BSNL Civil Division, Jodhpur.

-SD-  
Executive Engineer (C)

## Schedule of quantities

**Name of work:- Providing and laying RCC roof slab over pump room in M/W bldg camus shastrinagar, Chittorgarh.**

<u>S.N</u>	<u>Description of Items</u>	<u>QTY</u>	<u>UNIT</u>	<u>RATE</u>	<u>AMOUNT</u>
1	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :				
a)	1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size derived fro natural resources)	0.30	Cum		
2	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III)derived from natural sources : 3 graded stone aggregate 20 mm nominal sizederived from natural sources).	1.50	Cum		
3	Centering and shuttering including strutting, propping etc. and removal of form for :				
a)	Suspended floors, roofs, landings, balconies and access platform	14.00	Sqm		
4	12 mm cement plaster finished with a floating coat of neat cement of mix :				
a)	1:3 (1 cement: 3 fine sand)	35.00	Sqm		
5	Finishing walls with Acrylic Smooth exterior paint of required shade :				
a)	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm).	10.00	Sqm		
6	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
a)	One or more coats on old work.	7.00	Sqm		
7	Finishing walls with Acrylic Smooth exterior paint of required shade :				
a)	Old work (One or more coat applied @ 0.90 ltr/10 sqm).	60.00	Sqm		
8	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	2.15	Cum		
9	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	2.00	Cum		
10	credit of corroded reinforcement	60.00	kg		
11	Labour/ guard required at site for maintaining safety measures during the work execution to avoid incidents as directed by engineer incharge.	1	Nos.		
-				<b>Total</b>	

**Executive Engineer (C)  
BSNL Civil Division,  
Jodhpur**