

BHARAT SANCHAR NIGAM LIMITED
(A Govt. of India Enterprises)
O/o The Executive Engineer (Civil),
BSNL Civil Division, ,
Admin bldg .Subhash Nagar, Jodhpur – 342008.

NOTICE INVITING QUOTATIONS

The Executive Engineer (Civil), BSNL Civil Division- , Room No109 ,Admin bldg Ground floor .Subhash Nagar, Jodhpur, invites, on behalf of the Bharat Sanchar Nigam Limited, sealed/taped item rate quotations for the work of “Miscellaneous works such as lightening arrester, cable tray, earthing pit and unarmoured cable etc. in 40M. Tower at T.E. campus, Nimbahera, Chittorgarh,..” from the approved and Enlisted eligible Contractors in the appropriate class in BSNL (Civil Wing), DOT (Civil Wing), DOP (Civil Wing), CPWD, MES, Rajasthan state PWD (B&R) all having experience of similar type works.

The quotations / schedule of quantities may be had from this office during 11.00 hrs to 14 hrs upto dated 15.07.2024. The duly filled quotations should be reached to this office on dated 15.07.2024 at 15.00hrs, which will be opened on same day at 15:30hrs.

Estimated cost :- Rs. 57118/-

Conditions:

1. The work has to be finished within 10 days after issue of work order.
2. The rates quoted by the agency shall be inclusive of all types of taxes / levies / duty and GST as applicable by the Govt. including labour Cess and nothing extra shall be payable on such account. The Contractor, as service provider, shall be fully responsible for any default in payment of this tax.
3. The rates quoted by the agency shall be inclusive of 1 % (one percent) BOCW cess on the work done and shall be recovered from running / final bill as applicable on the building and other Construction workers welfare Cess Act, 1996 due to introduction of “The Building and other Construction Works Regulation of Employment and Conditions of Service Act 1996”.
4. Agency will comply the provisions of EPF & Misc. Provisions Act 1952, Employees Provident Fund Schemes 1952 and the ESI Act, 1948 in respect of labourers/employees engaged by them for performing the work.

NIQ NO. 08/ EE/BSNL-CIVIL/JDR/ 24-25/

Dated 12.07.2024

-SD-
Executive Engineer (C)
BSNL Civil Sub Division,
Jodhpur

File No 9(07)/EE/BSNL-CIVIL/JDR/ 24-25 / 81

Dated 12 .07.2024

Copy forwarded for information:-:

1. The Chief Engineer (C), BSNL Civil Rajasthan zone, Jaipur.
2. The Additional Chief Engineer (C), BSNL Civil Circle, Jodhpur/Jaipur,
3. The EE (C), BSNL Civil Division, Bikaner/Jaipur/Udaipur.
3. The IFA to Civil Division, O/o The GMTD, BSNL, Jodhpur
4. The SDE (C), BSNL Civil Sub Division –Jodhpur/ Barmer/Ajmer.
5. The Accounts Branch-I,II , O/o EE (C), BSNL Civil Division, Jodhpur.
6. Notice Board, O/o EE (C), BSNL Civil Division, Jodhpur.

-SD-
Executive Engineer (C)

Schedule of quantities

Name of work:-Miscellaneous works such as lightening arrester, cable tray, earthing pit and unarmoured cable etc. in 40M. Tower at T.E. campus, Nimbahera, Chittorgarh,

S.no	Description of items	Qty.	Unit	Rate	Amount
	SH:STEEL WORK				
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
(a)	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	265.00	Kg		
	SH:- Miscellaneous Work				
1	Providing parts of aviation light as necessary so as to satisfy aviation requirement:				
	(a) Providing and fixing PVC double insulated 2 core x 1.5 Sq.mm copper conductor / unarmoured power cable of approx. length 50M. (Finolex, Policab or equivalent) including removing damaged power cable and encasing new power cable in existing PVC conduit pipe. (b) Providing and fixing PVC conduit pipe of 20mm dia. of approved brand and manufacture all complete as per direction of Engineer Incharge. Note: - The rate includes for all the materials, labour and T&P etc. required for all the works as mentioned above.	1.00	One Job		
2	Earthing with galvanised (approximate 85 micron) G.I. plate of 600x600mm size as per drawing including accessories and providing necessary having locking enclosures with cover plates arrangement and watering pipe of 20mm dia. G.I. pipe (approx. length 2.00 M.), funnel etc. including filling charcoal or coke app. @250 Kg. per pit and salt @ 5Kg. per pit complete and required excavation and refilling as required and as directed by the Engineer Incharge.	1.00	One Job		
3	Providing and fixing lightening arrester of approved brand as directed by Engineer Incharge.	1.00	One Job		
				TOTAL	

**Executive Engineer (C)
BSNL Civil Division,
Jodhpur**