

No. EEC/BSNL/JPR/ 2024- 25/308

Dated 24.07.2024

NOTICE INVITING QUOTATION

NIQ No. NIQ-03/EEC/BSNL/JP//2024-25, Dated 24.07.2024


The Executive Engineer (Civil), BSNL CIVIL DIVISION, R1& R3 Type-IV Quarters, C- scheme Colony, Jaipur, invites, on behalf of the Bharat Sanchar Nigam Limited, sealed/taped item rate quotations for the work of " Dismantling and carriage of 40 M NBLW (GBT) tower from Piplai distt Sawaimadhapur to BSNL store at Gangapurcity, distt. Sawaimadhapur" from the approved and Enlisted eligible Contractors in the appropriate class in BSNL (Civil Wing), DOT (Civil Wing), DOP (Civil Wing), CPWD, MES, Rajasthan state PWD (B&R) all having experience of similar type works.

The quotation papers can be obtained from the office of the Executive Engineer (C), BSNL Civil Division QUARTER no R1/R3 P& T Colony C- scheme JAIPUR up to 1.00 PM on 27.07.2024 and duly filled quotations along with requisite papers will be received up to 3:00 Pm on 27.07.2024 and will be opened on the same day at 3:30PM.

Time Schedule- The time schedule for the work is fixed as 7(Seven) days from the date of award. The Firms shall strictly adhere to the time frame.

Conditions:-

1. The work has to be finished within 7days after issue of work order.
2. The rates quoted by the agency shall be inclusive of all types of taxes / levies / duty and GST as applicable by the Govt. including labour Cess and nothing extra shall be payable on such account. The Contractor, as service provider, shall be fully responsible for any default in payment of this tax.
3. The rates quoted by the agency shall be inclusive of 1% (one percent) BOCW cess on the work done and shall be recovered from running / final bill as applicable on the building and other Construction workers welfare Cess Act, 1996 due to introduction of "The Building and other Construction Works Regulation of Employment and Conditions of Service Act 1996".
4. Agency will comply the provisions of EPF & Misc. Provisions Act 1952, Employees Provident Fund Schemes 1952 and the ESI Act, 1948 in respect of labourers/employees engaged by them for performing the work.


Executive Engineer(C)
BSNL Civil Division
Jaipur

Copy to:


1. The Addl. C. E. (C), BSNL Civil Circle, Jaipur and Superintending Engineer (C), BSNL Civil Circle, Jodhpur.
2. The Executive Engineer BSNL, Civil Division, Udaipur, Jodhpur/Bikaner.
3. The E.E. Postal Civil Division. 1st floor C.P.M.G building, Sardar Patel Marg, Jaipur.
4. The E.E. CPWD, Jaipur.
5. The SDE BSNL, Civil Sub Division-I/II, Jaipur /ALW/JJN.
6. The AGM (MM), O/o CGMT, BSNL, Jaipur
7. The AGM (Plg) O/o PGMTD, BSNL, Jaipur
8. The A.O. (cash) O/o PGMTD, BSNL, Jaipur
9. Notice Board.

SCHEDULE OF QUANTITY

Name of the work : **Dismantling and carriage of 40 M NBLW (GBT) tower from Piplai distt Sawaimadhopur to BSNL store at Gangapurcity, distt. Sawaimadhopur.**

NIQ No. :-NIQ-03/EEC/BSNL/JP/2024-25

S.N.	Description of Item	Quantity	Unit	Quoted Rate in Figure (Rs)	Quoted Amount (Rs)
1	Dismantling and dismembering 40M (USO) GBT tower consisting of structural steel work bolted in built up section (Upto 40M height of Tower) including cutting of nuts/ bolts if required, dismembering of wave guide, platform ladder all complete as per direction of Engineer In Charge.	1.00	One Job		
	Notes :The items includes for the following and nothing extra shall be paid on this accounts.				
	(a) The agency shall take every precautions against the damages to the structure or near by structures while dismantling / dehoisting the tower.				
	(b) Necessary safety precautions to protect the human-lives, insurance coverage to the labours etc. shall be the sole responsibility of the agency.				
	(c) Nuts / bolts and washers dismantled shall be collected size-wise and kept in separate gunny bags				
	(d) Item includes all operations, tools & plants, equipments, machinery etc. required for the work as well as safety measures as per the relevent IS codes. This charges are for dismantling of tower of approximate weight of tower upto 2.25 Metric tonne.				
2	De-hoisting of the members as well as stacking and sorting out the tower members/nuts & bolts including making bundles in groups with binding strips and handing over all complete as per the direction of Engineer-in-charge.	1.00	One Job		
3	Extra for number painting on each member of dismentled above item no. 1 tower material etc as per direction of Enginner-in-Charge..	1.00	One Job		
4	Carriage of 40 M USO (GBT) material with antenna, ladder etc. including loading, unloading from Piplai, distt. Sawaimadhopur to BSNL Store at Gangapurcity, SawaiMadhopur around 40-50 Km lead approx weight 10 Metric tonne i/c handing over all material as directed.	1.00	One Job		
				Total Rs.	


Executive Engineer (C)
BSNL Civil Division,
Jaipur