

BHARAT SANCHAR NIGAM LIMITED
(A Govt. of India Enterprises)
O/o The Executive Engineer (Civil),
BSNL Civil Division, ,
Admin bldg .Subhash Nagar, Jodhpur – 342008.

NOTICE INVITING QUOTATIONS

The Executive Engineer (Civil), BSNL Civil Division- , Room No109 ,Admin bldg Ground floor .Subhash Nagar, Jodhpur, invites, on behalf of the Bharat Sanchar Nigam Limited, sealed/taped item rate quotations for the work of “ Roof Terrace Plaster and other Misc. work at rented RTT site Gandhi Nagar ,Ajmer.” from the approved and Enlisted eligible Contractors in the appropriate class in BSNL (Civil Wing), DOT (Civil Wing), DOP (Civil Wing), CPWD, MES, Rajasthan state PWD (B&R) all having experience of similar type works.

The quotations / schedule of quantities may be had from this office during 11.00 hrs to 14 hrs upto dated 05.08.2024. The duly filled quotations should be reached to this office on dated 05.08.2024 at 15.00hrs, which will be opened on same day at 15:30hrs.

Estimated cost :- Rs. 28237/-

Conditions:

1. The work has to be finished within 10(Ten) Days after issue of work order.
2. The rates quoted by the agency shall be inclusive of all types of taxes / levies / duty and GST as applicable by the Govt. including labour Cess and nothing extra shall be payable on such account. The Contractor, as service provider, shall be fully responsible for any default in payment of this tax.
3. The rates quoted by the agency shall be inclusive of 1 % (one percent) BOCW cess on the work done and shall be recovered from running / final bill as applicable on the building and other Construction workers welfare Cess Act, 1996 due to introduction of “The Building and other Construction Works Regulation of Employment and Conditions of Service Act 1996”.
4. Agency will comply the provisions of EPF & Misc. Provisions Act 1952, Employees Provident Fund Schemes 1952 and the ESI Act, 1948 in respect of labourers/employees engaged by them for performing the work.

NIQ NO. 10/ EE/BSNL-CIVIL/JDR/ 24-25/

Dated 01.08.2024

Executive Engineer (C)
BSNL Civil Sub Division,
Jodhpur

File No 9(07)/EE/BSNL-CIVIL/JDR/ 24-25 / 92

Dated 01 .08.2024

Copy forwarded for information:-:

1. The Chief Engineer (C), BSNL Civil Rajasthan zone, Jaipur.
2. The Additional Chief Engineer (C), BSNL Civil Circle, Jodhpur/Jaipur,
3. The EE (C), BSNL Civil Division, Bikaner/Jaipur/Udaipur.
3. The IFA to Civil Division, O/o The GMTD, BSNL, Jodhpur
4. The SDE (C), BSNL Civil Sub Division –Jodhpur/ Barmer/Ajmer.
5. The Accounts Branch-I,II , O/o EE (C), BSNL Civil Division, Jodhpur.
6. Notice Board, O/o EE (C), BSNL Civil Division, Jodhpur.

Executive Engineer (C)

Schedule of quantities

Name of Work:- Roof Terrace Plaster and other Misc. work at rented RTT site Gandhi Nagar ,Ajmer.					
S.No.	Description of Item	Quantity	Unit	Rate (Rs)	Amount
1	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement.				
a)	20 mm cement plaster	25.00	Sqm		
2	Extra for providing and mixing water proofing material in cement plaster work in proportion recommended by the manufacturers.	5.00	units		
3	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground , all complete as per directions of Engineer-In-Charge.				
a)	With cement mortar 1:4 (1 cement : 4 Coarse sand).	5.00	Sqm		
4	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	2.00	Cum		
5	Providing Beldar / Helper as and when required for attending at site for all work as directed by engineer incharge.	2.00	Nos.		
6	1 no. Pole mounted and 5 nos supported angles mounted in c.c 1:2:4 to be dismantle and repairing the same with cement plaster as directed by engineer incharge. Pole material received to be handing over to GSM Wing at site.	1	Job		
7	working cable tray i/c supported angles in C.C 1:2:4 to be removed/ demolishing from existng position with cutting ,grinding , welding etc wherever necessary . and fixing again in short lenth up to canopy wall surface and supporting the same i/c making hole in the M.S canopy wall and fixing the same as directed by engineer incharge.	1	Job		
8	Making khurra (450x300)mm in depressd at the mouth of Out let rain water pipes and finishing the same with cement plaster in neat finish as directed by engineer incharge	1	Job		
	Total				

**Executive Engineer(C)
BSNL Civil Division
Jodhpur**