

BHARAT SANCHAR NIGAM LIMITED

(A Govt. of India Enterprises)
O/o The Executive Engineer (Civil),
BSNL Civil Division, ,
Admin bldg .Subhash Nagar, Jodhpur – 342008.

NOTICE INVITING QUOTATIONS

The Executive Engineer (Civil), BSNL Civil Division- , Room No109 ,Admin bldg Ground floor .Subhash Nagar, Jodhpur, invites, on behalf of the Bharat Sanchar Nigam Limited, sealed/taped item rate quotations for the work of “Internal painting & Miscellaneous Civil works in Type IV/02 Staff Quarter at UIT Officers Colony in Jodhpur City..” from the approved and Enlisted eligible Contractors in the appropriate class in BSNL (Civil Wing), DOT (Civil Wing), DOP (Civil Wing), CPWD, MES, Rajasthan state PWD (B&R) all having experience of similar type works.

The quotations / schedule of quantities may be had from this office during 11.00 hrs to 14 hrs upto dated 05.08.2024. The duly filled quotations should be reached to this office on dated 05.08.2024 at 15.00hrs, which will be opened on same day at 15:30hrs.

Estimated cost :- Rs. 36114/-

Conditions:

1. The work has to be finished within 15(Fifteen) Days after issue of work order.
2. The rates quoted by the agency shall be inclusive of all types of taxes / levies / duty and GST as applicable by the Govt. including labour Cess and nothing extra shall be payable on such account. The Contractor, as service provider, shall be fully responsible for any default in payment of this tax.
3. The rates quoted by the agency shall be inclusive of 1 % (one percent) BOCW cess on the work done and shall be recovered from running / final bill as applicable on the building and other Construction workers welfare Cess Act, 1996 due to introduction of “The Building and other Construction Works Regulation of Employment and Conditions of Service Act 1996”.
4. Agency will comply the provisions of EPF & Misc. Provisions Act 1952, Employees Provident Fund Schemes 1952 and the ESI Act, 1948 in respect of labourers/employees engaged by them for performing the work.

NIQ NO. 12/ EE/BSNL-CIVIL/JDR/ 24-25/

Dated 01.08.2024

Executive Engineer (C)
BSNL Civil Sub Division,
Jodhpur

File No 9(07)/EE/BSNL-CIVIL/JDR/ 24-25 / 94

Dated 01 .08.2024

Copy forwarded for information:-:

1. The Chief Engineer (C), BSNL Civil Rajasthan zone, Jaipur.
2. The Additional Chief Engineer (C), BSNL Civil Circle, Jodhpur/Jaipur,
3. The EE (C), BSNL Civil Division, Bikaner/Jaipur/Udaipur.
3. The IFA to Civil Division, O/o The GMTD, BSNL, Jodhpur
4. The SDE (C), BSNL Civil Sub Division –Jodhpur/ Barmer/Ajmer.
5. The Accounts Branch-I,II , O/o EE (C), BSNL Civil Division, Jodhpur.
6. Notice Board, O/o EE (C), BSNL Civil Division, Jodhpur.

Executive Engineer (C)

Schedule of quantities

Name of the work : Internal painting & Miscellaneous Civil works in Type IV/02 Staff Quarter at UIT Officers Colony in Jodhpur City.

S.N.	Description of Item	Quantity	Unit	Rate	Amount (Rs)
	Sub-Head : Flooring				
1	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.				
1.a	40 mm thick with 20 mm nominal size stone aggregate	2.00	Sqm		
	Sub-Head : Finishing				
1	12 mm cement plaster finished with a floating coat of neat cement of mix :				
1.a	1:4 (1 cement: 4 fine sand)	15.00	Sqm.		
2	Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/ litre, of approved brand and of required shade and colour complete to give and even shade.				
a)	Old work (one or more coats)	250.00	Sqm		
b)	Two coat.	150.00	Sqm		
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	40.00	Sqm		
	Sub-Head : Repairs to Buildings				
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead :				

a)	With cement mortar 1:4 (1cement: 4 coarse sand).	4.00	Sqm		
	Sub-Head : Dismantling and Demolishing				
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
a)	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.10	Cum		
	SH: Miscellaneous				
1	Providing carpenter as and when required for attending complaints of carpentry works such as repair of doors , windows , cupboard shutters as per requirement on need basis for all jobs in one working day i/c cost of screws ,nails, fevicol clamps etc. (The material required for attending the complaints shall be arranged by the contractor at site and will be paid separately except cost of all T&P for attending the work shall be arranged by the contractor and nothing extra shall be paid.	1.00	Per day		
2	Providing Beldar /Helper /Sewer man as and when required for attending civil maintenance job for carpentry,plumbing and Sewerman job and for other miscellaneous works such as cleaning the colonies compound, roof etc. including the cost of ledder, tagari, phawra, bamboo etc.for all jobs in one working day.	1.00	per day		
	Total				

**Executive Engineer (C)
BSNL Civil Division
Jodhpur.**