

BHARAT SANCHAR NIGAM LIMITED
(A Govt. of India Enterprises)
O/o The Executive Engineer (Civil),
BSNL Civil Division, ,
Admin bldg .Subhash Nagar, Jodhpur – 342008.

NOTICE INVITING QUOTATIONS

The Executive Engineer (Civil), BSNL Civil Division- , Room No109 ,Admin bldg Ground floor .Subhash Nagar, Jodhpur, invites, on behalf of the Bharat Sanchar Nigam Limited, sealed/taped item rate quotations for the work of “**Urgent Sewerage line work in HIJK block in BSNL Colony vaishali nagar, Ajmer**” from the approved and Enlisted eligible Contractors in the appropriate class in BSNL (Civil Wing), DOT (Civil Wing), DOP (Civil Wing), CPWD, MES, Rajasthan state PWD (B&R) all having experience of similar type works.

The quotations / schedule of quantities may be had from this office during 11.00 hrs to 14 hrs upto dated 13.08.2024. The duly filled quotations should be reached to this office on dated 13.08.2024 at 15.00hrs, which will be opened on same day at 15:30hrs.

Estimated cost :- Rs. 52883/-

Conditions:

1. The work has to be finished within 10(Ten) Days after issue of work order.
2. The rates quoted by the agency shall be inclusive of all types of taxes / levies / duty and GST as applicable by the Govt. including labour Cess and nothing extra shall be payable on such account. The Contractor, as service provider, shall be fully responsible for any default in payment of this tax.
3. The rates quoted by the agency shall be inclusive of 1 % (one percent) BOCW cess on the work done and shall be recovered from running / final bill as applicable on the building and other Construction workers welfare Cess Act, 1996 due to introduction of “The Building and other Construction Works Regulation of Employment and Conditions of Service Act 1996”.
4. Agency will comply the provisions of EPF & Misc. Provisions Act 1952, Employees Provident Fund Schemes 1952 and the ESI Act, 1948 in respect of labourers/employees engaged by them for performing the work.

NIQ NO. 20/ EE(C)/BSNL-CIVIL/JDR/ 24-25/

Dated 09.08.2024

-SD-
Executive Engineer (C)
BSNL Civil Sub Division,
Jodhpu

File No 9(07)/EE/BSNL-CIVIL/JDR/ 24-25 / 21

Dated 09 .08.2024

Copy forwarded for information:-:

1. The Chief Engineer (C), BSNL Civil Rajasthan zone, Jaipur.
2. The Additional Chief Engineer (C), BSNL Civil Circle, Jodhpur/Jaipur,
3. The EE (C), BSNL Civil Division, Bikaner/Jaipur/Udaipur.
3. The IFA to Civil Division, O/o The GMTD, BSNL, Jodhpur
4. The SDE (C), BSNL Civil Sub Division –Jodhpur/ Barmer/Ajmer.
5. The Accounts Branch-I,II , O/o EE (C), BSNL Civil Division, Jodhpur.
6. Notice Board, O/o EE (C), BSNL Civil Division, Jodhpur.

-SD-
Executive Engineer (C)

Schedule of quantities

Name of Work:- Urgent Sewerage line work in HIJK block in BSNL Colony vaishali nagar, Ajmer					
.	Description of Item	Quantity	Unit	Rate (Rs)	Amount
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :				
a)	Cement mortar 1:4 (1 cement : 4 coarse sand)	3.00	Cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
a)	1:2:4 (1 cement : 2 coarse sand(zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	0.60	Cum		
b)	1:5:10 (1 cement : 5 coarse sand(zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	0.50	Cum		
3	12 mm cement plaster of mix :				
a)	1:4 (1 cement: 4 coarse sand)	30.00	Sqm		
4	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	2.00	Cum		
	SH:- Miscellaneous Items				
1	Providing Beldar /Helper as and when required for attending essential work as per need of site requirement	4.00	Each.		

2	Supplying and placing in position red sand stone slabs of thickness 30mm to 40 mm of required size as directed to cover GT chambers.	1.00	Sqm.		
3	Providing and fixing unplasticised Rigid PVC pipes conforming to IS : 13592 Type A, including connecting of Both manholes at the existing holes in working manhole and repairing the same of both the ends connected to manholes with cement mortar 1:3 satisfactorily as directed by engineer incharge.				
	(i)Single socketed pipes.				
a)	150mm diameter	20.00	Metre		
	Total:-				

Executive Engineer(C)
BSNL Civil Division
Jodhpur