BHARAT SANCHAR NIGAM LIMITED

(A Govt. of India Enterprises)
O/o The Executive Engineer (Civil),
BSNL Civil Division, ,
Admin bldg .Subhash Nagar, Jodhpur – 342008.

NOTICE INVITING QUOTATIONS

The Executive Engineer (Civil), BSNL Civil Division-, Room No109, Admin bldg Ground floor .Subhash Nagar, Jodhpur, invites, on behalf of the Bharat Sanchar Nigam Limited, sealed/taped item rate quotations for the work of "Repairing and painting work in Marketing Section and AGM S&M office in GMTD Campus, Ajmer.." from the approved and Enlisted eligible Contractors in the appropriate class in BSNL (Civil Wing), DOT (Civil Wing), DOP (Civil Wing), CPWD, MES, Rajasthan state PWD (B&R) all having experience of similar type works.

The quotations / schedule of quantities may be had from this office during 11.00 hrs to 14 hrs upto dated 13.08.2024. The duly filled quotations should be reached to this office on dated 13.08.2024 at 15.00hrs, which will be opened on same day at 15:30hrs.

Estimated cost :- Rs. 32107/-

Conditions:

- 1. The work has to be finished within 15(Fifteen) Days after issue of work order.
- The rates quoted by the agency shall be inclusive of all types of taxes / levies / duty and GST as applicable by the Govt. including labour Cess and nothing extra shall be payable on such account. The Contractor, as service provider, shall be fully responsible for any default in payment of this tax.
- 3. The rates quoted by the agency shall be inclusive of 1 % (one percent) BOCW cess on the work done and shall be recovered from running / final bill as applicable on the building and other Construction workers welfare Cess Act, 1996 due to introduction of "The Building and other Construction Works Regulation of Employment and Conditions of Service Act 1996".
- 4. Agency will comply the provisions of EPF & Misc. Provisions Act 1952, Employees Provident Fund Schemes 1952 and the ESI Act, 1948 in respect of labourers/employees engaged by them for performing the work.

NIQ NO. 21/EE/BSNL-CIVIL/JDR/24-25/

Dated 09.08.2024

- SD =
Executive Engineer (C)
BSNL Civil Sub Division,
Jodhpu

File No 9(07)/EE/BSNL-CIVIL/JDR/ 24-25 / 22

Dated 09.08.2024

Copy forwarded for information:-:

- 1. The Chief Engineer (C), BSNL Civil Rajasthan zone, Jaipur.
- 2. The Additional Chief Engineer (C), BSNL Civil Circle, Jodhpur/Jaipur,
- 3. The EE (C), BSNL Civil Division, Bikaner/Jaipur/Udaipur.
- 3. The IFA to Civil Division, O/o The GMTD, BSNL, Jodhpur
- 4. The SDE (C), BSNL Civil Sub Division -Jodhpur/ Barmer/Ajmer.
- 5. The Accounts Branch-I,II, O/o EE (C), BSNL Civil Division, Jodhpur.
- 6. Notice Board, O/o EE (C), BSNL Civil Division, Jodhpur.

-SD-

Executive Engineer (C)

Schedule of quantities

Schedule of quantities					
	of Work:- Repairing and painting work in Marlus , Ajmer.	keting Sect	ion and A	AGM S&M office in	n GMTD
S.No.	Description of Item	Quantity	Unit	Rate (Rs)	Amount
1	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement.				
a)	20 mm cement plaster	20.00	Sqm		
2	Extra for providing and mixing water proofing material in cement plaster work in proportion recommended by the manufacturers.	5.00	Units		
3	Pointing on stone work with cement mortar 1:3 (1 cement: 3 fine sand):				
a)	Flush/ Ruled pointing	10.00	Sqm		
4	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification.				
5	Two or more coats on old work.	100	Sqm		
6	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	80.00	Sqm		
7	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:				
8	One or more coats on old work.	50.00	Sqm		
a)	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground , all complete as per directions of Engineer-In-Charge.				
9	With cement mortar 1:4 (1 cement : 4 coarse sand).	2.00	Sqm		
a)	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	10.00	Sqm		
10	Providing and applying white cement based water proofwall care birla puttyof approved brand and manufacturer, to fill undulations/pits over the wall surface to prepare the surface even and smooth complete.	10.00	Kg		
	Total				